

BULLETIN NO: 14 RELEASE DATE: 27thFebruary 2020

Blocked, Locked & Definitely Stopped!



As we have known for some time the complex task of blocking and locking the side wall supporting the access lane is no quick fix!

The challenge being, that in order to stabilise the wall there is a slight risk of destabilising it during the work. The solution lies in installing a line of concrete pads along the base of the wall.

However, the secret lies in the sequence of digging out and concreting the pads. The disruption is minimised by a mathematical stagger that Carol Vorderman would be impressed by! So, for example pads 1, 5 and 10 might be done first and then after three days to let the concrete start setting pads 3, 7 and 11 are dug out. Clever stuff.

Now with the wall reinforcements underway, our hard-working builders have got the main perimeter foundations underway as our pictures highlight.

